BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO: 40**

SCHEDULE-B

NAME OF WORK: Construction of RCC deck in 4th cross Vishveshwaraiah Layout, Muneshwara Nagara & Soundarya Layout in Bagalagunte ward No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **MANJU B M**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of c10ds complete as per specifications. specification.	Cum	79.2	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
2	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	9.9	4100.0	Rupees Four Thousand One Hundred Only
3	Providing and constructing granite / trap I basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	29.7	4100.0	Rupees Four Thousand One Hundred Only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	33	4650.0	Rupees Four Thousand Six Hundred Fifty Only
5	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	33	78.44	Rupees Seventy Eight and Forty Four Paise Only

Signature of the Contractor

Executive Engineer

6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	20	7000.04	Rupees Seven Thousand and Four Paise Only
7	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	33	266.06	Rupees Two Hundred Sixty Six and Six Paise Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	79.2	78.21	Rupees Seventy Eight and Twenty One Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,